



## Cheyenne, WY

- Common clarifications are as follows:
  1. Equipment can be rented from Equipment Share with a signed contract. List of equipment must be provided with adequate notice prior to rental. No equipment from any other rental service will be allowed on Equipment Share property.
  2. The Fuel Island is provided/installed by others. Contractor to supply power to the Fuel Island only.
  3. The Pre-Engineered Metal Building will be supplied and delivered to the site by Equipment Share. Unloading, storage and complete installation of PEMB is to be performed by the GC.
  4. EV Charging Stations will be supplied by Equipment Share. Complete installation will be by the GC. Power to EV Stations is underground, to be installed prior to concrete.
  5. Electrical Panelboards, transformers and the manual transfer switch will be supplied by Equipment Share. Complete install will be by the Contractor.
  6. Exterior signage will be provided and installed by others.
  7. Security Fence requires 3-strand barbed wire.
  8. The Fire Sprinkler System is to be designed and installed by the Contractor.