



Farmington Pre-K Academy

Sub-Contract work scopes

3 coat stucco (includes rigid insulation install)

JAYNES CORPORATION GENERAL CONTRACTORS

2906 Broadway NE
Albuquerque, NM 87107
p 505.345.8591
f 505.345.8598
jaynescorp.com

FARMINGTON

900 Resource Avenue
Farmington, NM 87401
p 505.326.3354
f 505.325.6399

LAS CRUCES

1990 E. Lohman Ave
Las Cruces, NM 88001
p 575.526.6400
f 575.526.1495

DURANGO

65 Mercado Street
Ste 125
Durango, CO 81301
p 970.247.1831
f 970.247.0338

TEXAS

221 N. Kansas Street
Suite 700
El Paso, TX 79901
p 915.320.3739

- Install Thermax (spec'ed) rigid insulation per specifications over fluid applied water/air barrier around entire building, including overhangs. Rigid insulation will be cut and installed at metal wall panel locations "Z" furring strips.
- Tape seams of rigid insulation
- Install 3 coat stucco system per specifications
 - This scope of work includes erection of OSHA approved scaffolding system, the scaffolding will be erected per OSHA standards and OSHA regulations will be followed on a daily basis.
 - SWMP will be required at concrete mixer locations. This will be installed, maintained and removed by stucco contractor.
 - Daily cleanup will be required.

Disclaimer: The following is not intended to limit the subcontractors scope of work but to provide clarification and/or amplification of the work to be performed. Work is to be bid per plans, specifications, addenda, ASI's, RFI's, applicable codes, manufacturer's recommendations, trade standards and tolerances.

