



- Wall mounted data: x2 drops unless otherwise noted.
- 27 total locations
 - 68 total drops

- Ceiling mounted data: x2 drops unless otherwise noted.
- 3 total locations
 - 6 total drops

Requirements & Specifications:

- Mount owner furnished 2-post, 19" rack in IT room
- Provide & install ladder rack from wall to 2-post rack
- Provide & install Cat6A patch panels as needed in 2-post rack
- Provide and install blue Cat6A cabling
- Provide and install blue jacks at wall and patch panel
- Label each drop at jack and patch panel
- Test each drop with report delivered digitally to project manager
- If work is more than 1 week, provide update on a weekly basis, communicating progress, any potential delay