

ELECTRICAL SPECIFICATIONS:

GENERAL:

THESE ELECTRICAL DRAWINGS ARE DIAGRAMMATIC AND REQUIRE TRADESMEN SKILLED IN THE COMMERCIAL ELECTRICAL INDUSTRY TO COORDINATE THE NECESSARY INSTALLATIONS WITH OTHER TRADES. PROVIDE THE NECESSARY MATERIALS AND METHODS FOR THESE INSTALLATIONS, ADDITIONAL BLOCKING FOR CORRECT LIGHTING OUTLET AND DEVICE LOCATIONS, ETC. AT NO ADDITIONAL COST.

PROVIDE ALL SERVICE CONDUITS FOR TELEPHONE SERVICE AND VERIFY LOCATION OF UTILITY PEDESTAL / MANHOLE WITH LOCAL UTILITY REP. PROVIDE INSTALLATIONS PER SERVICE PROVIDER'S REQUIREMENTS.

VERIFY ALL EXISTING SITE AND PROJECT CONDITIONS. UTILITY COMPANY SERVICES AND PROVIDE INSTALLATIONS IN COMPLIANCE WITH THESE CONDITIONS. FIELD VERIFY ALL CONDITIONS AND MAKE ALLOWANCES FOR THESE CONDITIONS IN FINAL PRICING. ANY DISCREPANCIES SHALL BE REPORTED TO THE ENGINEER TO RESOLUTION PRIOR TO FINAL PRICING.

PROVIDE ALL NECESSARY INSTALLATION PLANNING, MATERIALS AND LABOR TO ENSURE A COMPLETE AND OPERABLE SYSTEM FOR EACH SYSTEM DESIGN INDICATED ON THE DRAWINGS AND THESE SPECIFICATIONS. ENSURE ALL WORK IS IN COMPLIANCE WITH THE CURRENT LOCAL AND NATIONAL ELECTRICAL CODES, FIRE AND SAFETY CODES. FURNISH TO THE G.C. ALL REQUIRED INSPECTION CERTIFICATES. THE CONTRACTOR IS RESPONSIBLE FOR ALL PERMITS, FEES, ETC. AND SHALL ENFORCE WORKER'S IDENTIFICATION PER LOCAL AND STATE LAWS.

ALL WORK SHALL BE PERFORMED IN A NEAT AND WORKMANSHIP LIKE MANNER, USING NEW MATERIALS WITH A ONE-YEAR WARRANTY MINIMUM. VERIFY FINISHES OF DEVICES, COVER PLATES, TRIMS, ETC. VERIFY APPROVED ROUTING OF SURFACE CONDUITS WHERE APPLICABLE.

THIS CONTRACTOR IS RESPONSIBLE FOR ACTUAL DISTANCES FOR FEEDERS AND CIRCUIT ROUTES. DO NOT USE THE FAULT CURRENT CALCULATION FOR ORDERING OR BIDDING FEEDERS. CONTRACTOR IS RESPONSIBLE FOR FUTURE COUNTS. DO NOT USE THE COMCHECK FOR BIDDING OR ORDERING LIGHTING FIXTURES.

MATERIALS AND METHODS:

ALL ELECTRICAL EQUIPMENT, DEVICES, LIGHT FIXTURES, CONTROLS, ETC. SHALL BE INSTALLED WITHIN MANUFACTURER'S REQUIREMENTS AND INSTRUCTIONS. ENSURE WORKING CLEARANCES FOR GEAR AND PANELS AND ACCESS TO CONNECTIONS OFF ALL TERMINATIONS.

BRANCH CIRCUITRY AND GROUNDING SHALL COMPLY WITH CODES FOR LOCATION, USE AND SPECIAL OCCUPANCIES. CONDUITS AND FITTINGS SHALL BE AS REQUIRED AND ALLOWED FOR EACH LOCATION.

COORDINATE WITH THE ARCHITECT AND ALL TRADES FOR INTENDED AND ACTUAL LOCATIONS OF EQUIPMENT, CEILING LAYOUTS AND MATERIALS, STRUCTURAL AND MECHANICAL EQUIPMENT AND DUCTS PRIOR TO ROUGH-IN AND ORDERING OF EQUIPMENT OR LIGHTING FIXTURES.

SUBMITTALS:

SUBMIT COMPLETE SHOP DRAWINGS OF ALL DISTRIBUTION GEAR, PANEL BOARDS AND LOAD CENTERS, FUSE TYPES AND BREAKERS WHERE SERIES RATING IS REQUIRED AND INDICATED ON THE DRAWINGS. CONTRACTOR TO CHECK AND CORRECT THE SUPPLIER'S SHOP DRAWINGS PRIOR TO SUBMITTING TO ENGINEER.

DISTRIBUTION GEAR AND PANELS:

PROVIDE A COMPLETE SERVICE DISTRIBUTION SYSTEM PER THE ONE LINE DIAGRAM. ENSURE CODE CLEARANCES, CONCRETE PADS, PROTECTION AND APPROVED LOCATIONS IN EQUIPMENT ROOMS. FUSES AND BREAKERS NOTED FOR SERIES RATING SHALL BE INSTALLED AS SPECIFIED TO ENSURE PROPER BREAKER BRACING PER THE FAULT CURRENT CALC. CONTRACTOR IS RESPONSIBLE FOR ADDITIONAL ENGINEERING DUE TO SUBSTITUTIONS OF WIRE TYPES THAT AFFECT ISC CALCULATIONS AND SERIES RATED STUDIES. ALL GEAR SHALL BE LABELED WITH PLAQUES AND PANEL INDEXES TYPED WITH ACCURATE LOADS IDENTIFIED.

PROVIDE FUSED AND NON-FUSED (WHERE APPROVED) DISCONNECT SWITCHES, RATED FOR LOCATION AND USE FOR ALL MECHANICAL AND SPECIAL EQUIPMENT.

PROVIDE SERVICE GROUNDING PER THE CURRENT N.E.C. ARTICLE 250. COORDINATE THE UPPER GROUNDING INSTALLATION PRIOR TO FOUNDATION POUR. ALL FEEDERS AND BRANCH CIRCUITS SHALL BE EQUIPPED WITH GROUNDING CONDUCTORS AND GROUNDED PER NEC 250. ENSURE GROUNDING JUMPERS AND BONDING THROUGHOUT THE SYSTEM.

ELECTRICAL DEVICES:

ALL DEVICES SHALL BE RATED FOR THE OVER CURRENT PROTECTION. VERIFY FINISHES AND DEVICE TYPES WITH ARCHITECT PRIOR TO ORDERING / BID. ENSURE GROUND FAULT DEVICES PER CODE AND ENSURE W.P. DEVICES ON EXTERIOR WALLS AND ON ROOF. ALL DEVICES SHALL BE RATED FOR USE IN SPECIAL OCCUPANCY USE AND LOCATIONS.

MECHANICAL EQUIPMENT:


REFER TO MECHANICAL AND PLUMBING DRAWINGS FOR EQUIPMENT LOCATIONS, EQUIPMENT SCHEDULE AND COORDINATE VOLTAGES AND NAMEPLATE OVER CURRENT PROTECTION. VERIFY UNITS FURNISHED WITH DISCONNECTS, STARTERS, ETC. ENSURE WIRE AND FUSE / BREAKER SIZES FOR UNITS. PROVIDE MAINTENANCE RECEPTACLES WHERE REQUIRED. ENSURE LIGHT, SWITCH AND GFI OUTLET IN ATTIC SPACES, CRAWL SPACES FOR MAINTENANCE.

FIRE ALARM AND DETECTION:

FIRE ALARM SYSTEM AND DETECTION IS CONSIDERED AS DESIGN-BUILD WITH THE CONTRACTOR'S SELECTED EQUIPMENT SUPPLIER. PROVIDE SHOP DRAWINGS AND COORDINATE WITH THE LOCAL CODE OFFICIALS FOR THE BUILDING TYPE AND OCCUPANCY FOR THE REQUIRED SYSTEM RULING. WHERE A NEW SYSTEM IS REQUIRED, PROVIDE DEDICATED POWER SUPPLY AND PHONE LINE CONDUIT TO THE TELEPHONE BOARD.

- GENERAL NOTES:
- REFER TO THE ARCHITECTURAL PLANS FOR ADDITIONAL WORK AND CLARIFICATIONS.
  - ALL POWER AND LIGHTING DEVICE LOCATIONS AND CONTROLS ARE AS PER THE ARCHITECTURAL DRAWINGS. ENSURE THAT ALL LOCATIONS AND HEIGHTS ARE AS PER NEC AND ADA REQUIREMENTS. ALL CIRCUITRY SHALL BE AS PER NEC.
  - ENSURE ALL MATERIALS AND METHODS OF CONSTRUCTION TO COMPLY WITH CURRENT N.E.C. (2017), I.B.C. NFPA, I.E.C.C. AND LOCAL ADOPTED OR AMENDED CODES.
  - COORDINATE WITH UTILITY COMPANY FOR FINAL TRANSFORMER SIZE, VOLTAGE, AND LOCATION. ANY DISCREPANCIES IN UTILITY TRANSFORMER SIZING AND / OR LOCATION SHALL BE REPORTED TO ENGINEER FOR REVISED FAULT CURRENT CALCULATIONS AND POSSIBLE RE-SPECIFICATION OF EQUIPMENT AIC RATINGS.
  - SUBMIT ELECTRICAL PLANS TO UTILITY COMPANY REPRESENTATIVE FOR FINAL REVIEW AND COORDINATION PRIOR TO WORK.
  - COORDINATE METERING INSTALLATION AND REQUIREMENTS WITH UTILITY COMPANY PRIOR TO WORK.
  - FIRE ALARM AND DETECTION DESIGN IS EXCLUDED. SUBMIT DRAWINGS TO FIRE PREVENTION CODE OFFICIALS FOR REVIEW AND SYSTEM DETERMINATION FOR THIS CONSTRUCTION AND CONDITIONS. IF REQUIRED, E.C. TO SUBMIT FIRE ALARM DETECTION AND NOTIFICATION SYSTEM DESIGN IN THE FORM OF SUPPLIER SHOP DRAWINGS FOR FIRE ALARM SEPARATE PERMIT.
  - CONTRACTOR SHALL COORDINATE DIRECTLY WITH LOW VOLTAGE CONSULTANT (TELE. DATA, AV, SECURITY / BURGLAR ALARM, ETC.) FOR SPECIFIC REQUIREMENTS FOR EACH RESPECTIVE SYSTEM. ANY EMPTY RACEWAYS REQUIRED BY THESE SYSTEMS SHALL BE COORDINATED DIRECTLY WITH THE CONSULTANT / SUPPLIER. ANY ADDITIONAL LINE VOLTAGE POWER REQUIRED AND NOT SHOWN ON THESE DRAWINGS SHALL BE REPORTED AND COORDINATED WITH ELECTRICAL ENGINEER.
  - ELECTRICAL CONTRACTOR SHALL UPSIZE ALL 120V BRANCH CIRCUITS EXCEEDING 75 LINEAR FEET OF RUN LENGTH TO #10 CU TO ACCOMMODATE VOLTAGE DROP.

- LEGEND
- JUNCTION BOX
  - SINGLE POLE SWITCH
  - THREE WAY SWITCH
  - WALL-BOX OCCUPANCY SENSOR
  - DUPLEX RECEPTACLE MIN. STD. WALL HEIGHT
  - 4-FLEX RECEPTACLE MIN. STD. WALL HEIGHT
  - SPECIAL PURPOSE RECEPTACLE
  - TELECOMM / DATA OUTLET W/ 3/4" C. STUB-UP (CONDUIT, BOX AND MUDRING BY E.C.)
  - T.V. COAX OUTLET PRE-WIRED BY SERVICE PROVIDER
  - MOTOR
  - DISCONNECT-RATED FOR USE
  - WEATHERPROOF
  - GROUND FAULT INTERRUPTER. PROTECT DOWNSTREAM
  - ABOVE COUNTER
  - MOUNT RECEPTACLE HORIZONTALLY.




PANEL "UNIT"									
208 / 120 VOLTS, 3 PHASE, 4 WIRE									
125 AMPS/MLO									
NEW, SURFACE									
AIC: 22,000 OR SERIES									
NOTES: MAX. 125 AMPS THIS PANEL									
CIRCUIT DESCRIPTION	V	CIRCUIT	PHASE	CIRCUIT	V	CIRCUIT	PHASE	CIRCUIT	DESCRIPTION
1 RESTROOM LT/RCPT/EF	312	20 GFI	0	20	1042	LIGHTING/FAN	2		
2 LOWER LEVEL RECEPTS	1080	20 GFI	0	20	1800	WATER HEATER	4		
3 LOWER LEVEL RECEPTS	1080	20 GFI	0	20	696	GARAGE DOOR	6		
7 MEZZANINE RECEPTS	1080	20 GFI	0	20		SPARE	8		
9 SPECIAL RCPT (#10,CU)	2000	30 GFI	0	20		SPARE	10		
11 SPARE	20	0	0	20		SPARE	12		
13 SPARE	20	0	0	20		SPARE	14		
15 SPARE	20	0	0	20		SPARE	16		
17 SPARE	20	0	0	20		SPARE	18		
19		0	0	30/3	2398	"RTU"	20		
21		0	0	2398	(#10, CU)		22		
23		0	0	2398			24		
PHASE A PHASE B PHASE C									
4.8 7.3 4.2									
CONV. KVA DEMAND % DEMAND KVA									
LIGHTING 0.0 125 0.0									
RECEPTACLE LOADS < 10 KVA 3.6 100 3.6									
RECEPTACLE LOADS > 10 KVA 0.0 50 0.0									
LARGEST MOTOR LOAD 7.2 125 9.0									
MOTOR LOADS 1.7 100 1.7									
HEAT 1.8 100 1.8									
MISCELLANEOUS LOAD 2 0.0 100 0.0									
MISC DED CIRCUITS 2.0 100 2.0									
MISCELLANEOUS LOAD 4 0.0 100 0.0									
TOTAL KVA: 18.1 TOTAL AMPS: 50.2									

PANEL "HB"									
208 / 120 VOLTS, 3 PHASE, 4 WIRE									
125 AMPS/MLO									
NEW, SURFACE									
AIC: 22,000 OR SERIES									
NOTES: MAX. 125 AMPS THIS PANEL									
CIRCUIT DESCRIPTION	V	CIRCUIT	PHASE	CIRCUIT	V	CIRCUIT	PHASE	CIRCUIT	DESCRIPTION
1 MONUMENT SIGN	1200	20	0	20	412	IRRIGATION / LIGHT	2		
3 "EUT" RISER RM	1500	20/2	0	20	250	FACP	4		
5	1500	7	0	20	470	SITE LIGHTING (V.I.A.P.C.)	6		
7 SPARE		20	0	20		SPARE	8		
9 SPARE		20	0	20		SPARE	10		
11 SPARE		20	0	20		SPARE	12		
13 SPARE		20	0	20		SPARE	14		
15 SPARE		20	0	20		SPARE	16		
17 SPACE			0			SPACE	18		
19 SPACE			0			SPACE	20		
21 SPACE			0			SPACE	22		
23 SPACE			0			SPACE	24		
PHASE A PHASE B PHASE C									
1.6 1.8 2.0									
CONV. KVA DEMAND % DEMAND KVA									
LIGHTING 0.0 125 0.0									
RECEPTACLE LOADS < 10 KVA 1.2 100 1.2									
RECEPTACLE LOADS > 10 KVA 0.0 50 0.0									
LARGEST MOTOR LOAD 0.0 125 0.0									
MOTOR LOADS 0.9 100 0.9									
HEAT 3.3 100 3.3									
MISCELLANEOUS LOAD 2 0.0 100 0.0									
MISC DED CIRCUITS 0.0 100 0.0									
MISCELLANEOUS LOAD 4 0.0 100 0.0									
TOTAL KVA: 5.3 TOTAL AMPS: 14.8									

FAULT CURRENT CALCULATIONS (UTILIZES THE BUSSMAN CALCULATION METHOD AND TABLES)						
CONTRACTOR IS RESPONSIBLE FOR ACTUAL FEEDER DISTANCES AND FIELD CONDITIONS IN PROJECT BID AND SCOPE.						
Description	Voltage	Ph	Length (FT)	# of Runt(s)	Conductor "C" value	Available Fault Current (ISC)
At Xcel Energy	208	1	49	2	21390	52,000
At "MS-B"	208	3	18	1	7301	33,064
At House Panel "HB"	208	3	18	1	7301	19,705
At Nearest Unit Panel	208	3	36	1	7301	14,034

600A "MS-B" SERVICE LOAD CALC		
LOAD DESIGNATION	LOAD (AMPS)	
UNIT PANELS (18.1 KVA X 7)	= 126.7 KVA	
HOUSE PANEL	= 5.3 KVA	
SUB TOTAL	= 132.0 KVA	
	= 366.8 AMPS	
	@ 208V, 3PH	



ELECTRICAL ONE LINE DIAGRAM

BUILDING "B" SITE ELECTRICAL PLAN  
SCALE: 1"=40'-0"

Date: 8/2/2021

Submission / Revision: FOR CONSTRUCTION

construction company, inc.

9808 East 62nd Avenue • Denver, Colorado 80216 • 303.987.5625 • Fax 303.987.3897 • www.dcbi.com

43330

8/2/2021

A NEW BUILDING FOR:

GARAGECONDOS at RACINE CIR.

SMALL BUSINESS SOLUTIONS

BUILDING B

6507 S. RACINE CIRCLE, CENTENNIAL CO 80111

Design Project No:

19-907

Drawing Title

BLDG "B" SITE ELEC & ONE LINE DIA.

Drawing No.

E1.0B



# GROUND LEVEL POWER PLAN

SCALE: 1/8"=1'-0"



**GARAGECONDOS at RACINE CIR.**  
A NEW BUILDING FOR:  
**SMALL BUSINESS SOLUTIONS**  
**BUILDING B**  
6507 S. RACINE CIRCLE, CENTENNIAL CO 80111

BLDG "B"  
LIGHTING  
PLANS

## E3.0B

