

GISD – ECPS Construction Cabling and Equipment 2024 RFP
Addendum number 2 dated September 16, 2024

The bid date for this Request for Proposals remains unchanged, September 30, 2024 at 2:00 PM. All other terms and conditions of the bid shall remain in full force and effect.

1. Reminder, that this project is a Prevailing Wage Project.
2. What certification standards do you want for this project?
 - a. Cabling should be installed using ANSI/TIA-568 standards. Restart
3. Preference on CAT6 cabling that is used?
 - a. Prefer that cabling is one of the following. We will consider other options. Please note what manufacture you are using.
 - i. Belden
 - ii. CommScope
 - iii. Hubbell
 - iv. ICC
 - v. Leviton
 - vi. Panduit
4. Do you want plenum rated cable?
 - a. Yes
5. Will work be completed during normal working hours?
 - a. Most of the work will be completed between 7:00 AM and 5:00 PM. Please note the cost for any 2nd shift or weekend work.
6. Are there drop ceilings throughout?
 - a. Most of the rooms have drop ceiling.
7. Are the promethean boards existing?
 - a. Yes
8. Who will be responsible for moving the boards
 - a. If this is something you're able to do, please include it in your quote (section 6 of bid form). Otherwise, Genesee ISD will find another vendor to move the boards.
9. Will phase 2 be a complete demo, including walls?
 - a. Most of the walls will remain. Only a few walls will be removed. The ceiling grid will be removed/replaced.
10. What type of cables do you want? Snagless or bootless?
 - a. Bootless.
11. What type of connectors you would like installed on the MDF to IDF fiber optic cable run?
 - a. LC connectors on both ends of the new fiber.
12. Will the existing fiber patch panel in the MDF be replaced?
 - a. No, this should stay as is. The fiber needs to stay up for all phases.
13. What size patch panel do you need for the fiber patch panels?
 - a. 1U is fine for fiber patch panel.