



Farmington Pre-K Academy

Sub-Contract work scopes

Plumbing

Drain and vent

JAYNES CORPORATION GENERAL CONTRACTORS

2906 Broadway NE
Albuquerque, NM 87107
p 505.345.8591
f 505.345.8598
jaynescorp.com

FARMINGTON

900 Resource Avenue
Farmington, NM 87401
p 505.326.3354
f 505.325.6399

LAS CRUCES

1990 E. Lohman Ave
Las Cruces, NM 88001
p 575.526.6400
f 575.526.1495

DURANGO

65 Mercado Street
Ste 125
Durango, CO 81301
p 970.247.1831
f 970.247.0338

TEXAS

221 N. Kansas Street
Suite 700
El Paso, TX 79901
p 915.320.3739

- Layout and trench all underground plumbing
- Install underground piping with proper sloping (PVC at underground)
- Shade all underground piping with sand or approved material
- Backfill all underground trenching with compaction and density testing up to final grade
- Confirm layout before slab placement
- All above grade piping shall be ductile Iron (see specifications) VE?

Water piping

- Install per specifications and drawings, including piping material, valves, hangers, etc..

Disclaimer: The following is not intended to limit the subcontractors scope of work but to provide clarification and/or amplification of the work to be performed. Work is to be bid per plans, specifications, addenda, ASI's, RFI's, applicable codes, manufacturer's recommendations, trade standards and tolerances.

