



City of Yonkers/Yonkers Public Schools
One Larkin Center – 3rd Floor
Yonkers, New York 10701
Tel: (914) 377-6035

Email: thomas.collich@yonkersny.gov

CITY OF YONKERS/YONKERS PUBLIC SCHOOLS
Purchasing

Mike Spano, Mayor
Tom Collich, Director

TO: PROSPECTIVE BIDDERS FEBRUARY 13, 2024
FROM: TOM COLLICH, PURCHASING DIRECTOR 3 PAGES
RE: BID NO. RFB-7092: INSIDE NETWORK CABLING SERVICES FOR THE 3RD, 9TH, 10TH, AND 11TH FLOORS AT 20 SOUTH BROADWAY, YONKERS NY
ADDENDUM NO. 2: CITY RESPONSE TO REQUESTS FOR INFORMATION

The contents of this addendum alter and amend the original bid requirements and take precedence over the related items therein. This addendum forms a part of the contract documents. Vendors must acknowledge receipt of all addenda when submitting their bids. Failure to acknowledge receipt may render a bid non-responsive and ineligible for award. Vendors are responsible for ensuring that they receive all addenda. All addenda will be posted on the Empire State Purchasing Group System (<http://www.empirestatebidsystem.com/>).

THE BID OPENING DATE IS EXTENDED TO FRIDAY, MARCH 1, 2024 AT 2:00 PM EST

BIDS RECEIVED AFTER 2:00 PM EST WILL NOT BE ACCEPTED

1. When is the start date?
City Response: As soon as possible, or 45 calendar days after bid opening.
2. Will access control cables all go to 9th floor?
City Response: No - 9, 10 and 11 go to the 9 th Floor. 3rd floor will have its own unit.
3. 3 Cabinets are in RFP but there's 4 IDFS?
City Response: COY will supply MDF for the 9th floor any bidder will supply 3 open 4 post rack for the other 3 floors
4. Any Manufacturer for the cabinets?
City Response: Yes but Racks
5. Do we have to use pre-terminated fiber?
City Response: NO – As long as it passes fiber connectivity tests
6. For fiber manufacturer is Quickdraw the manufacturer we must use?
City Response: NO
7. What is the 80ft of 3inch conduit for?
City Response: For fiber running from 9th floor to 3rd, 10h, 11th floor. Must comply with local building code
8. What is 1 ¼ white conduit used for if it's for drops that are on outside wall is wire mold V700 acceptable?
City Response: All wires will be inside the walls

9. Can we use Leviton manufacturer for jack's patch panels face plates etc. Spec sheets attached.
City Response: Yes
10. Is there a time restriction for drilling?
City Response: To be coordinated with building Management
11. Why do we need 8 fiber patch panels?
City Response: We need 4 fiber patch panels - one for each floor
12. What is the flat wire for?
City Response: connection to the conference room tables
13. What kind of amp do we need for the coax cables?
City Response: No amps needed
14. Parking? Will city of Yonkers provide a parking pass or will we need to include the \$22 per day per truck?
City Response: Contractor responsible for any payments.
15. What are the hours of operation? Can we work later? Saturdays?
City Response: 7am-5pm, unsure if an afterhours/weekend work permit is required. That is up to the landlord.
16. What is the time frame of each floor? Is there a completion date we need to be done by?
City Response: Once all approved plans are received, we will issue the project schedule which states completion of all floors by the end of June.
17. Certified payroll? Each week, month?
City Response: With every payment request.
18. Vertical core drills need sleeves CORRECT ? Horizontal just firestop?
City Response: Any penetrations through fire rated partitions, slabs, etc. require sleeves and fire stopping.
19. Each penetration through aluminum header needs a yellow Gromit CORRECT?
City Response: Correct
20. Mud rings are required on all aluminum studs for cable and faceplates due to no conduit?
City Response: Correct (5/8" GWB being used)
21. Are spacers required inside wall to protect cable from sheetrock screws?
City Response: Required, no..... Encouraged, yes. To comply with local code.
22. Are we providing open racks or cabinets in hub rooms?
City Response: Open racks
23. Do racks/ cabinets need to be grounded to building?
City Response: Yes
24. What make of patch panels are we using Ortronics or Siemens?
City Response: No Preference
25. Will Siemens maxjacks be used for all terminations?
City Response: Match jacks to patch panels
26. Total will be 211 dual cat 6 plenum cables?
City Response: Approximately 215 +/-

27. When is the start date?

City Response: As soon as possible, or 45 calendar days after bid opening.

28. Will access control cables all go to 9th floor?

City Response: No- 9, 10 and 11 go to the 9th Floor. 3rd floor will have its own unit

29. Will all coaxial cables go to 9th floor?

City Response: Yes

30. Will all camera cables go to 9th floor?

City Response: No- Camera cables will terminate on its respective floor

31. Will we need to terminate all these cables? Coaxial, camera, access control?

City Response: Coaxial- termination needed; Camera - terminations; Access Control - No termination needed

THE BID OPENING DATE IS EXTENDED TO FRIDAY, MARCH 1, 2024 AT 2PM EST

BID NO. RFB-7092: ADDENDUM NO. 2 – ACKNOWLEDGEMENT

Legal Name of Bidder: _____

Address: _____

**Print
Bidder's Representative:** _____

Title: _____

E-mail: _____

Website: _____

Telephone: _____ **Cell** _____

Signature: _____

Date: _____