Stacking and Storage Practices for Construction

When you are moving and storing materials at a construction site, there are a number of things that can go wrong, resulting in injuries like splinters, cuts, scrapes, or crushed fingers, hands and feet – and even death.

Potential Hazards

Workers can be injured by:

- Falling objects
- Improperly stacked materials
- Equipment and materials that may be sharp, abrasive or heavy

When manually moving materials, be aware of potential injuries such as:

- Strains and sprains
- Fractures and bruises
- Cuts and bruises

Moving, Handling and Storing Material

You should seek help moving a load when you cannot: properly grasp, lift or control it; see around or over it; or safely handle it.

Best Practices

- Ensure that NO part of the body is under a raised load
- Blocking materials should be large and strong to support the load
- Use handles or holders and tag lines to reduce finger pinching or smashing
- Use personal protective equipment (PPE):
 - For loads with sharp/rough edges, wear gloves/hand and forearm protection and eye and face protection
 - When loads are heavy or bulky, wear steel-toed safety shoes or boots
- Do not stack or store ANY materials closer than 18 inches (45 centimeters) from sprinkler heads

When moving materials with mechanical equipment:

- Avoid overloading equipment
- Note the equipment-rated capacity on each piece of equipment
- Pay attention to ground conditions
- Consider other employees near the path of travel

When using rough-terrain lifts, telehandlers and powered industrial trucks, the load must be:

- Centered on the forks
- As close to the mast as possible
- At or below capacity; never overload a lift truck
- At the lowest position for traveling
- Correctly piled, if stacked

Stacking Materials

Material	Best Practices
Lumber	 Remove nails before stacking Stack and level on solidly supported bracing Should be stable and self-supporting
Bricks	 Stacks should be no more than 7 feet (2 meters) high Taper back 2 inches (5 centimeters) for every foot (30 centimeters) of height above 4 feet (1.2 meters) Taper masonry blocks back 1/2 block for each tier above the 6-foot (1.8-meter) level
Bags and bundles	 Stack in interlocking rows to remain secure Stack bags by stepping back the layers and cross-keying the bags at least every 10 layers
Boxed materials	Band or hold in place using cross-ties or shrink wrap
Drums and barrels	 Stack symmetrically If stored on sides, block bottom tiers When stacked on end, put planks, sheets of plywood or pallets between each tier to make a firm, flat stacking surface When stacking materials two or more tiers high, chock the bottom tier on each side to prevent shifting in either direction
Hazardous materials	Some cannot be stored together; check with your supervisor or general contractor if you are unsure
Combustible materials	Store away from areas in which workers are welding or doing hot work
"Unstackable" materials	Unstackable materials (due to size, shape or fragility) may be safely stored in cargo containers or bins
Cylindrical materials	Example: structural steel, bar stock, polesStack and block
Pipes and bars	Do not store in racks which face walkways