



1 LEVEL 1 STRUCTURED CABLING PLAN AREA "C"
 1/8" = 1' - 0"
 SCALE: 1/8" = 1'-0"

GENERAL NOTES - CABLING

1. TC TO PROVIDE TELECOMMUNICATIONS BASKET TRAY AND J-HOOK SUPPORT FOR NETWORK CABLING. TC TO PROVIDE SEPARATE J-HOOK SUPPORT FOR SECURITY CABLING. KEEP MINIMUM 6" SEPARATION FROM NETWORK CABLING.
2. ALL NETWORK CABLING TO BE PLENUM RATED UOM. REFER TO SPECS FOR CABLE TYPES AND COLORS.
3. TC TO PROVIDE ALL SECURITY AND CCTV CABLING. REFER TO ONE-LINE DRAWING FOR TYPES. SECURITY DEVICES AND FINAL HOOK-UP BY SECURITY CONTRACTOR.
4. TC TO PROVIDE ALL INTERCOM/PAGING CABLING. REFER TO ONE-LINE DRAWING FOR TYPES. INTERCOM AND PAGING DEVICES AND FINAL HOOK-UP BY SECURITY CONTRACTOR.
5. TC TO PROVIDE NETWORK CABLING FOR AUDIO VISUAL DEVICES. AV CONTRACTOR TO PROVIDE CABLING BETWEEN DEVICES. FINAL EQUIPMENT HOOK-UP BY AV CONTRACTOR.
6. TC TO PROVIDE STAINLESS STEEL WALL PLATES WITH MOUNTING STUDS AND PANDUIT CAT 6 JACK FOR ALL WALL PHONE LOCATIONS.
7. TC TO PROVIDE RG-6 PLENUM COAX FOR TV OUTLETS TERMINATED USING COMPRESSION TYPE F-CONNECTORS. INSTALL F-81 FITTING AT FACEPLATE. FOR RUNS EXCEEDING 150', INSTALL RG-11 PLENUM COAX. ROUTE TO NEAREST TR. TV OUTLETS IN EOC TO ROUTE TO WALL BEHIND EQUIPMENT RACK WITH 15' SLACK.

SHEET NOTES - CABLING

1. NOT USED.
2. NOT USED.
3. NOT USED.
4. TC TO PROVIDE (1) CAT 6 FOR ELEVATOR EMERGENCY PHONE.
5. PANIC ALARM. MAY BE BUTTON OR INTERCOM DEPENDING ON LOCATION. TC TO ROUTE CABLE FOR DEVICE AS INDICATED ON DRAWING 1002.
6. PUSH BUTTON FOR DOOR RELEASE.

RNL
 1515 ARAPAHOE STREET
 TOWER III, SUITE 700
 DENVER, COLORADO 80202
 303 295 1717 f
 303 292 0845 f

Technology Plus
 INCORPORATED
 COMMUNICATIONS TECHNOLOGY PLANNING
 Aurora, Colorado 80012
 Ph: 303-340-8228
 Fax: 303-340-8233

RNL - ARCHITECT
 RNL - LANDSCAPE ARCHITECT
 RNL - MECHANICAL, PLUMBING, ELECTRICAL
 SA MIRO - STRUCTURAL ENGINEER
 LUND PARTNERSHIP - CIVIL ENGINEER
 TECHNOLOGY PLUS - COMMUNICATIONS

**CITY OF COMMERCE CITY
 CIVIC AND JUSTICE CENTER**

7887 EAST 60TH AVENUE
 COMMERCE CITY, COLORADO 80022

FOR CONSTRUCTION	05.15.06
Technology Coordination	03.20.06
DESIGN DEV - GMP	01.06.06
SCHEMATIC DESIGN	10.07.05

PROJECT No: 1021-1895-02
 DATE: 1.06.06
 SCALE: AS SHOWN

COMMUNICATIONS
 Structured Cabling Plan

T101C